

System Impact Study SPP-2002-097
For Transmission Service
Requested By
Tenaska Power Service Co.

From AEPW To ERCOTE

For a Reserved Amount Of 9 MW
From 6/1/02
To 6/1/03

SPP Coordinated Planning

SPP IMPACT STUDY (#SPP-2002-097) May 15, 2002 Page 1 of 10

# **Table of Contents**

1.	EXECUTIVE SUMMARY	3
2.	INTRODUCTION	4
3.	STUDY METHODOLOGY	5
	A. DESCRIPTION	5
	B. MODEL UPDATES	5
	C. Transfer Analysis	
4.	STUDY RESULTS	6
	A. STUDY ANALYSIS RESULTS	6
	TABLE 1 – SPP FACILITY OVERLOADS CAUSED BY THE AEPW TO ERCOTE 9 MW TRANSFER	
	TABLE 2 - NON - SPP FACILITY OVERLOADS CAUSED BY THE AEPW TO ERCOTE 9 MW TRANSFER	7
	TABLE 3 – PREVIOUSLY ASSIGNED AND IDENTIFIED SPP FACILITIES IMPACTED BY THE AEPW TO	
	ERCOTE 9 MW Transfer	
	TABLE 4 – AMOUNT OF CONFIRMED RESERVATION 260690 NEEDED FOR CURTAILMENT	8
5	CONCLUSION	Q

### 1. Executive Summary

Tenaska Power Service Co. (TNSK) has requested a system impact study for long-term Firm Point-to-Point transmission service from AEPW to ERCOTE. The period of the transaction is from 6/1/02 to 6/1/03. The request is for OASIS reservation 356989 for 50 MW. OASIS reservation 356989 is the renewal of reservation 239038 that was accepted for 9 MW and can only be renewed for 9 MW.

The principal objective of this study is to identify system problems and potential system modifications necessary to facilitate the additional 9 MW transfer while maintaining system reliability.

New overloads caused by the 9 MW transfer were identified along with determining the impact of the transfer on any previously assigned and identified facilities.

The AEPW to ERCOTE 9 MW transfer impacts facilities that have been identified as limiting constraints for previously studied transfers. Due to the inability to upgrade these limiting constraints within the reservation period using normal construction practices, the ATC is zero for the requested AEPW to ERCOTE 9 MW transfer.

Partial curtailment of one of Tenaska's previously confirmed ERCOTE to Entergy 50 MW transfers (Oasis Reservations 260690, 260692, or 260694) was looked at as an option to relieving the impact on the limiting facilities caused by the AEPW to ERCOTE 9 MW transfer.

## 2. Introduction

Tenaska Power Service Co. (TNSK) has requested an impact study for transmission service from AEPW to ERCOTE.

The principal objective of this study is to identify the restraints on the SPP Regional Tariff System that may limit the transfer to less than 9 MW. This study includes steady-state contingency analyses (PSS/E function ACCC) and Available Transfer Capability (ATC) analyses.

The steady-state analyses consider the impact of the 9 MW transfer on transmission line loading and transmission bus voltages for outages of single and selected multiple transmission lines and transformers on the SPP system.

### 3. Study Methodology

### **A.** Description

Two analyses were conducted to determine the impact of the 9 MW transfer on the system. The first analysis was conducted to identify any new overloads caused by the 9 MW transfer. The second analysis was done to ensure that available capacity exists on previously identified circuits.

The first analysis was to study the steady-state analysis impact of the 9 MW transfer on the SPP system. The second step was to study Available Transfer Capability (ATC) of the facilities identified in the steady-state analysis impact. The steady-state analysis was done to ensure current SPP Criteria and NERC Planning Standards requirements are fulfilled. The Southwest Power Pool (SPP) conforms to the NERC Planning Standards, which provide the strictest requirements, related to thermal overloads with a contingency. It requires that all facilities be within emergency ratings after a contingency.

The second analysis was done to determine the impact of the transfer on previously assigned and identified facilities.

### **B.** Model Updates

SPP used five seasonal models to study the AEPW to ERCOTE 9 MW transfer. The SPP 2002 Series Cases: 2002 Summer Peak, 2002 Fall Peak, 2002/03 Winter Peak, 2003 April Minimum, and 2003 Spring Peak were used to study the impact of the 9 MW transfer on the SPP system during the transaction period of 6/1/02 to 6/1/03.

The chosen base case models were modified to reflect the most current modeling information. The cases were modified to reflect future firm transfers during the request period that were not already included in the January 2002 base case series models.

### C. Transfer Analysis

Using the created models and the ACCC function of PSS\E, single and select double contingency outages were analyzed. Then full AC solution was used to obtain the most accurate results possible. Any facility overloaded, using MVA ratings, in the transfer case and not overloaded in the base case was flagged. The PSS/E options chosen to conduct the Impact Study analysis can be found in Appendix A.

### 4. Study Results

### A. Study Analysis Results

<u>Tables 1, 2,</u> and <u>3</u> contain the analysis results of the System Impact Study. The tables identify the seasonal case in which the event occurred; the emergency rating of the overloaded circuit (Rate B), the contingent loading percentage of circuit with and without the studied transfer, the estimated ATC value using interpolation if calculated, any SPP identification or assignment of the event, and any solutions received from the transmission owners.

<u>Table 1</u> shows the new SPP facility overloads caused by the 9 MW transfer. Available solutions are given in the table.

<u>Table 2</u> documents overloads on Non SPP Regional Tariff participants' transmission systems caused by the 9 MW transfer.

<u>Table 3</u> documents the 9 MW transfer impact on previously assigned and identified SPP facilities. Available solutions are given in the table.

<u>Table 1</u> – SPP Facility Overloads caused by the AEPW to ERCOTE 9 MW Transfer

Study Year	From Area To Area	Branch Over 100% Rate B	Rate B	BC %Loading	TC %Loading	Outaged Branch That Caused Overload	ATC	Solution
02SP		NONE					9	
02FA		NONE					9	
02WP		NONE					9	
03AP		NONE					9	
03G		NONE					9	

<u>Table 2</u> – Non - SPP Facility Overloads caused by the AEPW to ERCOTE 9 MW Transfer

Study Year	From Area To Area	Branch Over 100% Rate B	Rate B	BC %Loading	TC %Loading	Outaged Branch That Caused Overload
02SP		NONE				
02FA		NONE				
02WP		NONE				
03AP		NONE				
03G		NONE				

<u>Table 3</u> – Previously Assigned and Identified SPP Facilities Impacted by the AEPW to ERCOTE 9 MW Transfer

Study Year	From Area To Area	Branch Over 100% Rate B	Rate B	BC %Loading	TC %Loading	Outaged Branch That Caused Overload	ATC	Assignment
02SP	KACP-KACP	<b>LACYGNE TO STILWELL. 350 KV</b> 57981 LACYGNE7 345 to 57968 STILWEL7 345 CKT 1	1251	101.6	101.7	<b>LACYGNE TO WEST GARDNER, 350 KV</b> 57981 LACYGNE7 345 to 57965 W.GRDNR7 345 CKT1	0	SPP Flowgate, Upgrade Assigned to SPP-2000-108, Date Required 6/1/05: Build Parallel LaCygne to Stilwell 350 kV line Construction Lead-time 36 Months
526.	10.00.10.00.	5.66. 2.6. 6.42. 6.6 6.6 6.6 6.6 6.6 6.6 6.6 6.6 6.6 6	1201	10110		3.30. 2.6. 3.42. 3.8 63.30		
02FA		NONE					50	
02WP		NONE					50	
03AP		NONE					50	
03G		NONE					50	

<u>Table 4</u> – Amount of Confirmed Reservation 260690 Needed for Curtailment

Overloaded Facility	Date Curtailment Needed	ERCOTE to EES % Response	AEPW to ERCOTE % Response	*ATC (MW) Needed	**Amount of ERCOTE to EES 9 MW transfer (Oasis Reservation 260690) Needed for Curtailment	ATC (MW) Available for AEPW to ERCOTE transfer after curtailment of 260690
LACYGNE TO STILWELL. 345 KV	6/1/02-10/1/02	3.0	3.0	9	9	9

<sup>\*</sup>Amount of Curtailment Needed = ATC Needed (MW) \*AEPW to ERCOTE % Response / AEPW to ERCOTE % Response

### 5. Conclusion

The requested 9 MW of firm point-to-point transmission service was studied for the time period of the request (6/1/02-6/1/03).

The previously assigned and identified facilities limit the ATC to zero due to the inability to upgrade the constraints as required. The acceptance of the 9 MW AEPW to ERCOTE transfer is dependent on the partial curtailment of the previously confirmed ERCOTE to EES 50 MW transfer (Oasis Reservation 260690).

For the 2002 Summer (6/1/02-10/1/02), the ATC is zero due the loading of the La Cygne to Stilwell 345kV line. The estimated construction lead-time for the La Cygne to Stilwell overload is 36 months. The partial curtailment of a confirmed 50 MW transfer from ERCOTE to EES may be used as an option to relieving these overloads.

The amount of curtailment required to accept the requested AEPW to ERCOTE 9 MW transfer is 9 MW of the confirmed ERCOTE to EES 50 MW transfer, OASIS reservation 260690. Without the availability of this curtailment, the requested AEPW to ERCOTE 9 MW transfer will be limited to an ATC of 0 MW for the 2002 Summer.

### PSS/E CHOICES IN RUNNING LOAD FLOW PROGRAM AND ACCC

### BASE CASES:

Solutions - Fixed slope decoupled Newton-Raphson solution (FDNS)

- 1. Tap adjustment Stepping
- 2. Area interchange control Tie lines only
- 3. Var limits Apply immediately
- 4. Solution options  $\underline{X}$  Phase shift adjustment
  - \_ Flat start
  - \_ Lock DC taps
  - Lock switched shunts

#### ACCC CASES:

Solutions – AC contingency checking (ACCC)

- 1. MW mismatch tolerance -0.5
- 2. Contingency case rating Rate B
- 3. Percent of rating 100
- 4. Output code Summary
- 5. Min flow change in overload report 1mw
- 6. Excld cases w/ no overloads form report YES
- 7. Exclude interfaces from report NO
- 8. Perform voltage limit check YES
- 9. Elements in available capacity table 60000
- 10. Cutoff threshold for available capacity table 99999.0
- 11. Min. contng. case Vltg chng for report 0.02
- 12. Sorted output None

### **Newton Solution:**

- 1. Tap adjustment Stepping
- 2. Area interchange control Tie lines only
- 3. Var limits Apply automatically
- 4. Solution options  $\underline{X}$  Phase shift adjustment
  - \_ Flat start
  - \_ Lock DC taps
  - \_ Lock switched shunts