



SPP *Southwest
Power Pool*

**Facility Study
For
Generator Interconnection
Requests
GEN-2014-004/IFS-2014-001-04
GEN-2014-013/IFS-2014-001-07**

*SPP Generator
Interconnection Studies*

*(#GEN-2014-004/IFS-2014-001-04)
(#GEN-2014-013/IFS-2014-001-07)*

February 2015

Revision History

Date	Author	Change Description
01/27/2015	SPP	Draft Facility Study Report Issued
02/03/2015	SPP	Final Facility Posted for GEN-2014-004/IFS-2014-001-04

Summary

Nebraska Public Power District (NPPD) performed a detailed Facility Study at the request of Southwest Power Pool (SPP) for Generation Interconnection request GEN-2014-004/IFS-2014-001-04 (3.96 MW, Wind Generation) located in Jefferson County, Nebraska and GEN-2014-013/IFS-2014-001-07 (73.5 MW, Wind Generation) located in Antelope and Boone Counties, Nebraska. Interconnection Customer, GEN-2014-004/IFS-2014-001-04 is an Energy Resource Interconnection Service (ERIS) only SPP GI Interconnection Request. Interconnection Customer, GEN-2014-013/IFS-2014-001-07 is an Energy Resource Interconnection Service (ERIS) and Network Resource Interconnection Service (NRIS) SPP GI Interconnection Request. ERIS and/or NRIS SPP GI Interconnection Service types do not guarantee transmission service rights in the SPP transmission system. SPP has proposed the in-service date for GEN-2014-004/IFS-2014-001-04 and GEN-2014-013/IFS-2014-001-07 will be after a fully executed Generation Interconnection Agreement (GIA) is filed for the corresponding Interconnection Request. Full Interconnection Service will require the Network Upgrades listed in the "Other Network Upgrades" section. The request for interconnection was placed with SPP in accordance with SPP's Open Access Transmission Tariff, which covers new generation interconnections on SPP's transmission system.

Phases of Interconnection Service

It is not expected that interconnection service will require phases however, interconnection service will not be available until all interconnection facilities and network upgrades can be placed in service for GEN-2014-004/IFS-2014-001-04 or GEN-2014-013/IFS-2014-001-07.

Interconnection Customer Interconnection Facilities

The Interconnection Customer GEN-2014-004/IFS-2014-001-04 generation is a SPP Interconnection Service amount increase of 3.96MW to GEN-2011-018 and GEN-2013-008. The GEN-2011-018, GEN-2013-008, and GEN-2014-004/IFS-2014-001-04 facility consists of forty-four (44) 1.79 G.E. wind turbines for total Interconnection Service of 78.76MW. The 34.5kV collector system for this wind farm is planned to be connect to one (1) 115/34.5kV Interconnection Customer owned and maintained transformer at the Interconnection Customer owned substation. An approximate three (3) mile 115kV transmission circuit will connect the Interconnection Customer owned substation to the NPPD owned 115kV Steele City Substation. The Interconnection Customer will be responsible for all of the transmission facilities connecting the customer owned substation to the Point of Interconnection (POI), at NPPD owned 115 kV bus at Steele City Substation. The Interconnection Customer, GEN-2014-004/IFS-2014-001-04, will also be responsible for any equipment located at the Customer substation necessary to maintain a power factor of 0.95 lagging to 0.95 leading at the POI.

The GEN-2014-013/IFS-2014-001-07 facility consists of forty-two (42) 1.75 G.E. XLE wind turbines for total Interconnection Service of 73.5MW. The 34.5kV collector system for this wind farm is planned to be connect to one (1) 230/34.5kV Interconnection Customer owned and maintained transformer at the Interconnection Customer owned substation. An approximate twenty-two (22) mile 230kV transmission circuit will connect GEN-2014-013/IFS-2014-001-07 to the existing GEN-2008-086N02 customer substation. GEN-2014-013/IFS-2014-001-07 will utilize the GEN-2008-086N02 generator lead, which is an approximate twenty-four (24) mile 230kV transmission circuit connecting the Interconnection Custer requests to the NPPD owned 230kV Meadow Grove 230kV Substation. The Interconnection Customer, GEN-2014-013/IFS-2014-001-07, will be responsible

for all of the transmission facilities connecting the customer owned substation to the Point of Interconnection (POI), at NPPD owned 230 kV bus at Meadow Grove Substation. The Interconnection Customer, GEN-2014-013/IFS-2014-001-07, will also be responsible for any equipment located at the Customer substation necessary to maintain a power factor of 0.95 lagging to 0.95 leading at the POI.

Transmission Owner Interconnection Facilities and Non-Shared Network Upgrades

The Transmission Owner has verified that the Steele City 115kV substation and associated terminal equipment is acceptable for the GEN-2014-004/IFS-2014-001-04 Interconnection Facilities. GEN-2014-004/IFS-2014-001-04 is currently responsible for approximately \$0 of Interconnection Facilities and Non-Shared Network Upgrades.

Table 1: GEN-2014-004/IFS-2014-001-04 TOIF and Non-Shared Network Upgrades

Transmission Owner Interconnection Facilities and Non-Shared Network Upgrades Description	Allocated Cost (\$)	Allocated Percent (%)	Total Cost (\$)
Interconnection Substation - Transmission Owner Interconnection Facilities 115kV Substation work	\$0	100%	\$0
Total	\$0	100%	\$0

The Transmission Owner has verified that the Meadow Grove 230kV substation and associated terminal equipment is acceptable for the GEN-2014-013/IFS-2014-001-07 Interconnection Facilities. GEN-2014-013/IFS-2014-001-07 is currently responsible for approximately \$0 of Interconnection Facilities and Non-Shared Network Upgrades.

Table 2: GEN-2014-013/IFS-2014-001-07 TOIF and Non-Shared Network Upgrades

Transmission Owner Interconnection Facilities and Non-Shared Network Upgrades Description	Allocated Cost (\$)	Allocated Percent (%)	Total Cost (\$)
Interconnection Substation - Transmission Owner Interconnection Facilities 230kV Substation work	\$0	100%	\$0
Total	\$0	100%	\$0

Shared Network Upgrades

The Interconnection Customer, GEN-2014-004/IFS-2014-001-04, was studied with in the DISIS-2014-001 cluster impact study and the latest DISIS-2014-001-1 restudy. Based on the latest restudy, the Interconnection Customer is allocated \$0 for Shared Network Upgrades at this current time.

Table 3: GEN-2014-004/IFS-2014-001-04 Shared Network Upgrades

Shared Network Upgrades Description	Allocated Cost (\$)	Allocated Percent (%)	Total Cost (\$)
Currently GEN-2014-004/IFS-2014-001-04 is not allocated Shared Network Upgrades	\$0	n/a	\$0
Total	\$0	n/a	\$0

The Interconnection Customer, GEN-2014-013/IFS-2014-001-07, was studied with in the DISIS-2014-001 cluster impact study and the latest DISIS-2014-001-1 restudy. Based on the latest restudy, the Interconnection Customer is allocated \$0 for Shared Network Upgrades at this current time.

Table 4: GEN-2014-013/IFS-2014-001-07 Shared Network Upgrades

Shared Network Upgrades Description	Allocated Cost (\$)	Allocated Percent (%)	Total Cost (\$)
Currently GEN-2014-013/IFS-2014-001-07 is not allocated Shared Network Upgrades	\$0	n/a	\$0
Total	\$0	n/a	\$0

If higher queued Interconnection Customers withdraw from the queue, suspend or terminate their GIA, restudies will have to be conducted to determine the Interconnection Customers' allocation of Shared Network Upgrades. All studies have been conducted on the basis of higher queued interconnection requests and the upgrades associated with those higher queued interconnection requests being placed in service.

Other Network Upgrades

Certain Other Network Upgrades are currently not the cost responsibility of the Customer but will be required for full Interconnection Service. Currently, the NPPD facility study has identified the following Other Network Upgrades are required for GEN-2014-004/IFS-2014-001-04 and GEN-2014-013/IFS-2014-001-07:

- Hoskins – Neligh East 345/115kV Project, assigned as a 2014 Integrated Transmission Plan Near Term (ITPNT) Reliability Upgrade with an on schedule in-service date of 6/1/2016¹
- Neligh East – County Line – Battle Creek 115kV rebuild upgrade assigned to DISIS-2013-002-2 Customer
- Twin Church – Dixon County – Hoskins 230kV Clearance Increase assigned to DISIS-2010-002 and DISIS-2011-001 Customers

Depending upon the status of higher or equally queued customers, the Interconnection Customer's in-service date is at risk of being delayed or their Interconnection Service is at risk of being reduced until the in-service date of these Other Network Upgrades.

¹ Please refer to footnote 1 for the SPP-NTC link.

Conclusion

Interconnection Service for GEN-2014-004/IFS-2014-001-04 and GEN-2014-013/IFS-2014-001-07 will be after a fully executed Generation Interconnection Agreement (GIA) is filed for the corresponding Interconnection Request.

The Interconnection Customer, GEN-2014-004/IFS-2014-001-04, is responsible for \$0 of Transmission Owner Interconnection Facilities and Non-Shared Network Upgrades. At this time, the Interconnection Customer, GEN-2014-004/IFS-2014-001-04, is allocated \$0 for Shared Network Upgrades. At this time the total allocation of costs assigned to GEN-2014-004/IFS-2014-001-04 for Interconnection Service for 3.96Mws is estimated at \$0.

The Interconnection Customer, GEN-2014-013/IFS-2014-001-07, is responsible for \$0 of Transmission Owner Interconnection Facilities and Non-Shared Network Upgrades. At this time, the Interconnection Customer, GEN-2014-013/IFS-2014-001-07, is allocated \$0 for Shared Network Upgrades. At this time the total allocation of costs assigned to GEN-2014-013/IFS-2014-001-07 for Interconnection Service for 73.5MWs is estimated at \$0.

**DISIS-2014-001-1
GENERATION INTERCONNECTION
FACILITY STUDY**

**SPP GEN-2014-004 3.96 MW at Steele Flats 115 kV Substation
SPP GEN-2014-013 73.5 MW at Prairie Breeze 230 kV Substation**

JANUARY 2015

**PREPARED FOR:
SOUTHWEST POWER POOL**

**PREPARED BY:
NEBRASKA PUBLIC POWER DISTRICT OPERATIONS
TRANSMISSION ASSET PLANNING
T&D ASSET MANAGEMENT
T&D ENGINEERING**



Nebraska Public Power District

"Always there when you need us"

Table of Contents

EXECUTIVE SUMMARY	
1.0	INTRODUCTION 1
2.0	STUDY SCOPE..... 2
2.1	Overview..... 2
2.2	Loadflow Analysis 3
2.3	Short Circuit Analysis..... 6
2.4	Detailed Cost Estimates and Project Schedule 7
3.0	MODEL DEVELOPMENT..... 8
4.0	STUDY CRITERIA..... 10
5.0	LOADFLOW ANALYSIS 11
5.1	Phase 1 Results (System-wide N-1 Screening)..... 11
5.2	Phase 2 Results (System-wide Multiple Element Screening)..... 14
5.3	Phase 3 Results (Local Area Full Accredited Generation Capacity N-1 & N-2 Contingency Analysis)..... 17
5.3.1	Phase 3 – N-1 Contingency Analysis Results..... 17
5.3.2	Phase 3 – Multiple Element Contingency Analysis Results..... 17
5.3.3	Phase 3 – Independent N-2 Contingency Analysis Results 18
5.4	Phase 4 Results (System-wide N-1 Screening with Transfers) 20
6.0	SHORT CIRCUIT ANALYSIS..... 22
6.1	Model Development..... 22
6.2	Study Methodology..... 23
6.3	Results..... 23
7.0	DETAILED COST ESTIMATES AND PROJECT SCHEDULE 24

Executive Summary

The *NPPD DISIS-2014-001-1 Facility Study* was performed to document the reliability impacts of generation projects proposed to interconnect to the NPPD transmission system. These projects have developed through the SPP Definitive Interconnection System Impact Study process and have advanced to the facility study stage. SPP has requested that NPPD perform the Facility Study associated with the generation interconnection projects listed below:

<u>Project</u>	<u>MW</u>	<u>Type</u>	<u>Point-of-Interconnection</u>
GEN-2014-004	+3.96	Wind	Steel Flats 115 kV Substation
GEN-2014-013	+73.5 77.46	Wind	Prairie Breeze 230 kV Substation

SPP entered into a facility study agreement with each of the generation interconnection customers and subsequently requested that NPPD perform the Facility Study for each request. In response to the SPP request, NPPD has performed a Facility Study for the generation interconnection requests. This facility study (DISIS-2014-001-1) included a detailed loadflow analysis and short circuit analysis. The Facility Study also includes detailed cost estimates and estimated project schedules for the interconnection and network upgrades identified in the System Impact and Facility Study.

The Loadflow Analysis documents the steady-state performance of the network following the generation interconnection projects. The loadflow analysis was split into four phases.

Phase 1 of the loadflow analysis was a system intact and N-1 contingency analysis of the Nebraska transmission system in accordance with NERC Standards TPL-001 and TPL-002. The Phase 1 screening did not identify any significantly impacted facilities for system intact or N-1 conditions. The North Platte – Stockville 115 kV line was identified as an impacted constraint, however, the impact was less than the cutoff threshold for generation interconnection studies. The Phase 1 screening did not discover any impacted bus voltages outside of limits for system intact or N-1 conditions.

Phase 2 of the loadflow analysis involved a comprehensive multiple element contingency analysis of the Nebraska transmission system. The Phase 2 screening did not identify any significantly impacted facilities for Category C or Category D conditions. The North Platte – Stockville 115 kV line was identified as an impacted constraint, however, the impact was less than the cutoff threshold for generation interconnection studies. The Phase 2 screening did not discover any impacted bus voltages outside of limits for Category C or Category D conditions.

Phase 3 of the loadflow analysis evaluated the local area transmission capacity with respect to delivering the fully accredited generating capability out of the area at off-peak load levels. The Phase 3 loadflow analysis was performed to evaluate the system state for the worst-case N-1, stuck breaker, and N-2 contingencies in the area of the generation project. There were no impacted transmission facility overloads or bus voltages outside

of limits discovered in the Phase 3 screening for NERC category A, B, C, and D contingencies. There were several category C and D contingencies that resulted in facility overloads; however, the impact was less than the cutoff threshold for generation interconnection studies. These facility overloads were documented in the facility study. This phase did identify several independent N-2 contingencies that would require prior outage generation limitations of the proposed generation interconnection projects. These prior outage limitations would be developed through an operational study and/or operational guides if the projects continue to be developed. The limiting prior outages are listed below:

Limiting Prior Outage Facilities

1. Bloomfield – Gavins Point 115 kV
2. Neligh East – Hoskins 345 kV
3. Neligh East 345/115 kV Transformer
4. Neligh East – County Line 115 kV
5. North Hebron – Fairbury 115 kV
6. North Hebron – Carleton Junction 115 kV
7. Gavins Point – Yankton Junction 115 kV
8. Gavins Point – Spirit Mound 115 kV

Phase 4 of the loadflow analysis evaluated the transmission system with respect to worst-case north-to-south transfer conditions across Nebraska. The Phase 4 analysis was performed to evaluate worst-case N-1 contingencies under these highly stressed transfer conditions. Overall, there were multiple transmission facility overloads and voltage issues discovered in the Phase 4 screening that were associated with west-east and north-south transfer limitations in Nebraska. The limitations are expected to be marginally improved by the future transmission projects being developed in Nebraska (GGs-Thedford-Holt 345 kV, Nebraska City-Sibley 345 kV), however, these constraint relief benefits should be minimal and the issues documented in this phase of the study will persist if all the proposed generation interconnection projects move forward.

The Short Circuit Analysis was performed to evaluate the fault interrupting capability of existing devices in the area and protection coordination issues following the generation interconnection projects. The results of this analysis showed that there were no protective devices that would be subject to replacement due to the proposed interconnection projects.

Overall, the *NPPD DISIS-2014-001-1 Facility Study* documents the performance of the network following the addition of the generation interconnection project and network upgrades. The Facility Study has documented the transmission plan required for interconnection to the NPPD transmission system and the details of this plan are listed on the following pages.

DISIS-2014-001-1 Interconnection Plan

Interconnection Facilities

- GEN-2014-004 Interconnection Facilities – Expansion (if required) of the customer-owned Steele Flats Wind 115 kV substation to accommodate the interconnection of the GEN-2014-004 wind project.
- GEN-2014-013 Interconnection Facilities – Expansion (if required) of the customer-owned Prairie Breeze 230 kV substation to accommodate the interconnection of the GEN-2014-013 wind project.

1.0 Introduction

In November 2014, NPPD was notified that several generation interconnection requests in the SPP generation interconnection queue had advanced to the facility study stage. These generation interconnection requests were evaluated by SPP in the Definitive Interconnection System Impact Study (DISIS-2014-001). The generation interconnection requests are listed below:

<u>Project</u>	<u>MW</u>	<u>Type</u>	<u>Point-of-Interconnection</u>
GEN-2014-004	3.96	Wind	Steel Flats Wind expansion
GEN-2014-013	<u>73.5</u>	Wind	Prairie Breeze Wind expansion
	77.46		

SPP entered into a facility study agreement with each of the generation interconnection customers and subsequently requested that NPPD perform the Facility Study for each request. In response to the SPP request, NPPD has performed a Facility Study for the generation interconnection requests.

This facility study (DISIS-2014-001-1) includes a detailed loadflow and short circuit analysis. The Facility Study also includes detailed cost estimates and estimated project schedules for the interconnection and network upgrades identified in the System Impact Study and Facility Study. The System Impact Study did not identify any network upgrades required for interconnection of the new generation projects.

2.0 Study Scope

2.1 Overview

This Facility Study will evaluate the impact of the requested generation interconnection projects on the NPPD transmission system. This study will evaluate generator interconnection requests in the SPP Generator Interconnection Queue studied in the SPP Definitive Interconnection System Impact Study, SPP DISIS-2014-001-1, and progressed to the facilities study stage. The GI projects on the NPPD transmission system included in the DISIS-2014-001-1 study are as follows:

<u>Project</u>	<u>MW</u>	<u>Type</u>	<u>Point-of-Interconnection</u>
GEN-2014-004	+3.96	Wind	Steel Flats 115 kV Substation
GEN-2014-013	+73.5	Wind	Prairie Breeze 230 kV Substation
	77.46		

NPPD will perform a Facility Study the generation interconnection requests that includes a detailed loadflow and short circuit analysis. The Facility Study also includes detailed cost estimates and estimated project schedules for the interconnection and network upgrades identified in the System Impact Study and Facility Study. No interconnection facilities or network upgrades were identified in the System Impact Study as required for this generation interconnection project

At the time of this facility study, there were several active generation interconnection requests in the SPP GI queue in the Nebraska area. Due to time constraints, this facility study must proceed assuming the following generation interconnection projects and associated network upgrades remain active projects in the SPP GI process. If any of these GI projects or network upgrades withdraw from the SPP GI queue, then a re-study of this DISIS-2014-001-1 facility study will be required. The previously-queued GI projects and network upgrades in the Nebraska area are as follows:

Request	MW	Area	Point-Of-Interconnection	Status
GEN-2008-123N	89.7	NPPD	Rosemont 115 kV Substation	Under Development
GEN-2010-051	200	NPPD	Tap Twin Church - Hoskins 230kV	Under Development
GEN-2011-027	120	NPPD	Tap Twin Church - Hoskins 230kV	Under Development
GEN-2010-041	10.5	OPPD	S 1399 161kV	Under Development
GEN-2013-008	1.2	NPPD	Steele Flats 115 kV Collector Substation	Under Development
GEN-2013-014	25.5	NPPD	Rosemont 115 kV Substation	On Suspension
GEN-2013-002	50.6	LES	Sheldon - Folsom & Pleasant Hill 115kV CKT 2	Facility Study
GEN-2013-019	73.6	LES	Sheldon - Folsom & Pleasant Hill 115kV CKT 2	Facility Study
GEN-2013-032	204	NPPD	Neligh East / Antelope 115 kV Substation	IA Pending

Previously allocated interconnection facilities & network upgrades

- Rosemont 115 kV substation (for GEN-2008-123N)
- Dixon County 230 kV substation (for GEN-2010-051)
- Upgrade Twin Church-DixonCounty-Hoskins 230kV line
- Neligh East / Antelope 115 kV substation expansion (for GEN-2013-32)
- Neligh East – County Line – Battle Creek 115 kV upgrade

This facility study will assess the new system state with the generation interconnection requests. The facility study will also identify any additional transmission issues that would require mitigation to meet mandatory NERC reliability standards following the addition of the generation interconnections and network upgrades. The Facility Study will include the following study phases:

1. Loadflow Analysis
2. Short Circuit Analysis

The loadflow analysis will be an assessment of the transmission system following the addition of the generation interconnection project and network upgrades. The loadflow analysis will evaluate the transmission system for compliance with NERC Reliability Standards and identify any thermal and voltage issues that would require mitigation. The short circuit analysis will evaluate the impacts of the generation interconnection project and network upgrades on existing fault currents in the area and determine if the capability of existing fault interrupting devices are adequate.

The intent of the facility study is to perform a detailed assessment of the proposed generation interconnection facility and associated transmission and validate adherence to system reliability criteria. This study will be performed in accordance with NERC Reliability Standards and the criteria set forth under those standards. This facility study will document the required transmission facility interconnection plan for the proposed uprate and will be performed in accordance with the methodologies described in NPPD's Facility Connection Requirements Document.

2.2 Loadflow Analysis

NPPD Transmission Planning will perform a loadflow analysis to screen the steady state performance of the network following the addition of the generation interconnection project and network upgrades. The powerflow models used for the loadflow analysis will be 2014 Series SPP MDWG models. These models will represent expected near-term system conditions with the generation interconnection projects and will adequately represent a variety of worst-case seasonal conditions. The powerflow models utilized for the analysis will be:

2016 Spring Load Case
2016 Summer 100% Peak Load Case
2016 Winter 100% Peak Load Case
2020 Spring Load Case
2020 Summer 100% Peak Load Case
2020 Winter 100% Peak Load Case

The base SPP MDWG powerflow models will be updated with planned transmission facility additions in the area of the generation interconnection requests.

The loadflow study will be split into four phases:

Phase 1 : System-wide Single Contingency N-1 Analysis

Phase 2 : System-wide Multiple Element Contingency N-2 Analysis

Phase 3 : Local Area Full Accredited Generation Capacity N-1 & N-2 Contingency Analysis

Phase 4 : System-wide Single Contingency N-1 Analysis under heavy transfer conditions

PHASE 1: This Phase is considered a comprehensive single contingency analysis of the entire Nebraska subregion. Every single element rated from 115 kV – 345 kV in the NPPD, OPPD, and LES areas plus ties will be outaged and monitored through activity ACCC. The results of the contingency screening will be assessed and documented. Phase 1 will also further investigate all critical contingencies identified from the ACCC contingency screening. Phase 1 will be utilized to document the performance characteristics of the system in accordance with NERC Reliability Standards.

PHASE 2: This Phase is considered a comprehensive multiple element contingency analysis of the entire Nebraska region. Multiple element contingencies rated from 115 kV – 345 kV will be outaged and monitored through activity ACCC. The multiple element contingencies consist of stuck breaker contingencies and double circuit tower contingencies identified by Nebraska transmission owners and utilized during MRO and SPP screening processes. The results of the contingency screening will be assessed and documented. Phase 2 will also further investigate all critical contingencies identified from the ACCC contingency screening comparison. Phase 2 will be utilized to document the performance characteristics of the system in accordance with NERC Reliability Standards.

PHASE 3: This Phase will evaluate the impacts of worst case N-1 single contingency and independent N-2 double contingency conditions for the local area transmission outlet paths associated with the generation interconnection projects. The 2014 Series 2014

Winter Peak Load case will be utilized to show the impacts of the worst case local area contingencies. All of the local area generation included in the study will be redispatched off-system. The purpose of this Phase will be to document sufficient generator outlet transmission capacity for the generation interconnection requests concurrent with the existing approved accredited generation in the area.

This Phase will be used to evaluate the Nebraska area transmission capacity with respect to delivering the fully accredited generating capability out of the local area resources for load levels at and above 70% of peak. The Winter Peak Load case is approximately 70% of summer peak for the Nebraska region. To stress the generation outlet capacity, the maximum accredited generation is modeled in Nebraska and exported into the surrounding MAPP & SPP regions. The following maximum accredited net generation levels will be modeled in this phase:

GEN-2014-004 (Steele Flats)	=	3.96 MW
<u>GEN-2014-013 (Prairie Breeze)</u>	=	<u>73.5 MW</u>
GEN-2013-032 (Neligh East)	=	204.0 MW
GEN-2008-123N (Rosemont)	=	89.7 MW
GEN-2010-051 (DixonCo)	=	200.0 MW
GEN-2011-027 (DixonCo)	=	120.0 MW
GEN-2013-002 (HallamN)	=	50.6 MW
GEN-2010-041 (Flat Water exp.)	=	10.5 MW
GEN-2013-019 (HallamN)	=	73.6 MW
GEN-2013-008 (Steele Flats)	=	1.2 MW
GEN-2013-014 (Rosemont)	=	25.5 MW
Hebron #1	=	52.0 MW
Deshler Units #1-4	=	2.3 MW
Belleville Units #4-8	=	13.9 MW
Fairbury Units #2-3	=	15.3 MW
Red Cloud Units #1-5	=	4.0 MW
Sheldon #1	=	105.0 MW
Sheldon #2	=	120.0 MW
Hallam #1	=	52.0 MW
Beatrice Power Station #1	=	80.0 MW
Beatrice Power Station #2	=	80.0 MW
Beatrice Power Station #3	=	90.0 MW
Nebraska City #1	=	652.0 MW
Nebraska City #2	=	682.0 MW
Cass County #1	=	161.5 MW
Cass County #2	=	161.5 MW
Flat Water Wind	=	60.0 MW
Atchison County Wind	=	144.0 MW
Laredo Ridge Wind	=	80.0 MW
TPW Petersburg Wind	=	40.5 MW
Broken Bow Wind	=	80.0 MW
Broken Bow Wind II	=	75.0 MW

Bloomfield Crofton Hills Wind	=	42.0 MW
Bloomfield Elkhorn Ridge Wind	=	81.0 MW
Steele Flats Wind	=	73.6 MW
Ainsworth Wind	=	75.0 MW
Prairie Breeze Wind	=	200.0 MW
Columbus Hydro #1-3	=	45.0 MW
Columbus ADM Co-Gen #1	=	75.0 MW
Gavins Point #1-3	=	92.0 MW
Ft. Randall #1-6	=	347.0 MW

All of the incremental generation adjustments were made to external Nebraska resources to effect these schedules. Additional non-firm schedules into the MAPP and SPP regions made up the transfers. This type of operational mode is highly unlikely, but was utilized to demonstrate the transmission capacity available to deliver the fully accredited generation out of the Nebraska area under emergency conditions.

PHASE 4: This Phase is considered a comprehensive single contingency analysis of the entire Nebraska subregion under transfer conditions. This Phase will assess the performance of the NPPD transmission system under heavy west-to-east and north-to-south transfer conditions. Transfer cases will be established to evaluate the system with the new generation interconnection projects. Every single element rated from 115 kV – 345 kV in the NPPD, OPPD, and LES areas plus ties will be outaged and monitored through activity ACCC. The results of the contingency screening will be assessed and documented. Phase 4 will also further investigate all critical contingencies identified from the ACCC contingency screening. Phase 4 will be utilized to document the performance characteristics of the system in accordance with NERC Reliability Standards.

2.3 Short Circuit Analysis

The purpose of the Short Circuit Analysis will be to evaluate the impacts of the proposed generation interconnection projects on the existing substation equipment fault duty ratings in the area. The substations to be evaluated are those electrically close to the interconnection points of the generation interconnection projects.

The Short Circuit Analysis will include short circuit calculations, an evaluation of the adequacy of existing circuit breaker interrupting ratings and an evaluation of the adequacy of the fault withstand capability of other substation equipment located at the monitored substations. The Short Circuit Analysis will be performed by NPPD Engineering Protection & Control personnel.

2.4 Detailed Cost Estimates & Project Schedule

NPPD Engineering, Asset Management, and Project Management departments will review any additional transmission upgrades identified in the SPP DISIS-2014-001-1 facility study. Detailed cost estimates and project schedules will be developed by these groups to implement the proposed transmission upgrades using standard NPPD construction and procurement practices. If any additional transmission upgrades are identified in this facility study, a detailed cost estimate and project schedule for these additional upgrades will be developed and provided as required.

3.0 Model Development

Overview

This study was conducted using Rev 32.2.1 of Power Technology Inc.'s (PTI's) Power System Simulator (PSS/E) software package and the following SPP 2013 Series MDWG powerflow models:

2016 Spring Load Case
2016 Summer 100% Peak Load Case
2016 Winter 100% Peak Load Case
2020 Spring Load Case
2020 Summer 100% Peak Load Case
2020 Winter 100% Peak Load Case

The powerflow models were updated to include the generation interconnection projects and network upgrades as well as the latest transmission upgrades documented in the latest regional transmission plans.

The powerflow models were updated based on previously approved future generation interconnection projects in the area. The following future generation interconnection projects were included in the base powerflow models:

GEN-2013-032 (Neligh East)	=	204.0 MW
GEN-2008-123N (Rosemont)	=	89.7 MW
GEN-2010-051 (DixonCo)	=	200.0 MW
GEN-2011-027 (DixonCo)	=	120.0 MW
GEN-2013-002 (HallamN)	=	50.6 MW
GEN-2010-041 (Flat Water exp.)	=	10.5 MW
GEN-2013-019 (HallamN)	=	73.6 MW
GEN-2013-008 (Steele Flats)	=	1.2 MW
GEN-2013-014 (Rosemont)	=	25.5 MW

The proposed future generation interconnection projects were dispatched off-system to other BA's in the SPP footprint. The new generation interconnection projects listed below were then added to the models and dispatched at 100%. The total output (77.46 MW) from the new generation interconnection projects was dispatched off-system to all other balancing authorities within the SPP footprint on a pro rata basis.

GEN-2014-004 (Steele Flats)	=	3.96 MW
GEN-2014-013 (Prairie Breeze)	=	73.5 MW

Wind Generation Models

Each of the new wind generation interconnection projects were modeled with a +/- 0.95 power factor range with voltage control capability at the designated point-of-interconnection. Some of the new projects may have a larger reactive power range available, but the reactive capability of each generation interconnection project was limited to +/- 0.95 power factor to match the power factor requirements identified in the system impact study.

4.0 Study Criteria

Facility Loading Criteria

Overloads of equipment are defined as greater than 100% of the normal continuous rating (Rate A).

Voltage Criteria

Normal steady-state voltage levels are defined as 0.95 to 1.05 pu. Emergency steady-state voltage levels are defined as 0.90 – 1.10 pu and may be utilized for less than 30 minutes.

5.0 Loadflow Analysis

5.1 Phase 1 Results (System-wide N-1 Screening)

PSS/E activity ACCC was used as a screening tool on each of the base cases to identify those contingencies which deserve closer study. ACCC analyzed the system by sequentially taking each transmission element greater than 100kV in the NPPD, OPPD, and LES areas out of service. Transmission facilities in the NPPD, OPPD, and LES areas were then monitored for violations of loading or bus voltage criteria. Contingencies which resulted in facility loadings or bus voltages outside of acceptable limits will be discussed in the summary of each case. The Phase 1 ACCC analysis is performed to assess the performance of the transmission system following the addition of the generation interconnection projects and proposed new network upgrades according to TPL-001 and TPL-002 standards.

Phase 1 analysis further addressed contingencies flagged in the screened ACCC run with additional AC powerflow analysis as required. In the NPPD area, there are loadflow solution issues associated with voltage regulation bandwidths. Consequently, most of the capacitors and reactors are modeled as fixed mode switched shunts, which must be manually switched to achieve optimal voltage profiles.

Powerflow activities VCHK and RATE were used to identify voltage and loading issues in the NPPD, OPPD, and LES areas for the full AC solution contingency runs. Activity VCHK produced a listing of those buses whose voltage magnitude was greater than 1.05 PU, followed by a listing of buses whose voltage was less than 0.95 PU. Activity RATE reported any branch whose current loading, including line charging and line connected shunt components, exceeded the specified percentage of RATE A.

Phase 1 – 2016 Spring

System Intact Results (TPL-001):

There were no impacted transmission facility overloads or bus voltages outside of limits under system intact or base case conditions for the 2016 Spring model.

N-1 Contingency Results (TPL-002):

There were no impacted transmission facility overloads or bus voltages discovered outside of limits under N-1 conditions for the 2016 Spring model.

Phase 1 – 2016 Summer Peak

System Intact Results (TPL-001):

There were no impacted transmission facility overloads or bus voltages outside of limits under system intact or base case conditions for the 2016 Summer Peak model.

N-1 Contingency Results (TPL-002):

The North Platte – Stockville 115 kV line was found to overload for loss of the GGS – Red Willow 345 kV line (111.9%). Without the new wind projects, this overload would be 110.6% so the impact to the constraint is less than the cutoff threshold. This residual impact should be noted as it does adversely impact the constraint and could be an issue in transmission service studies and/or real-time operations.

There were no impacted bus voltages discovered outside of limits under N-1 conditions for the 2016 Summer Peak model.

Phase 1 – 2016 Winter Peak

System Intact Results (TPL-001):

There were no impacted transmission facility overloads or bus voltages outside of limits under system intact or base case conditions for the 2016 Winter Peak model.

N-1 Contingency Results (TPL-002):

There were no impacted transmission facility overloads or bus voltages discovered outside of limits under N-1 conditions for the 2016 Winter Peak model.

Phase 1 – 2020 Spring

System Intact Results (TPL-001):

There were no impacted transmission facility overloads or bus voltages outside of limits under system intact or base case conditions for the 2020 Spring model.

N-1 Contingency Results (TPL-002):

There were no impacted transmission facility overloads or bus voltages discovered outside of limits under N-1 conditions for the 2020 Spring model.

Phase 1 – 2020 Summer Peak

System Intact Results (TPL-001):

There were no impacted transmission facility overloads or bus voltages outside of limits under system intact or base case conditions for the 2020 Summer Peak model.

N-1 Contingency Results (TPL-002):

There were no impacted transmission facility overloads or bus voltages outside of limits under N-1 conditions for the 2020 Summer Peak model.

Phase 1 – 2020 Winter Peak

System Intact Results (TPL-001):

There were no impacted transmission facility overloads or bus voltages outside of limits under system intact or base case conditions for the 2020 Winter Peak model.

N-1 Contingency Results (TPL-002):

There were no impacted transmission facility overloads or bus voltages discovered outside of limits under N-1 conditions for the 2020 Winter Peak model.

Phase 1 Results Summary

The Phase 1 screening did not identify any significantly impacted facilities for system intact or N-1 conditions. The North Platte – Stockville 115 kV line was identified as an impacted constraint, however, the impact was less than the cutoff threshold for generation interconnection studies. The Phase 1 screening did not discover any impacted bus voltages outside of limits for system intact or N-1 conditions.

5.2 Phase 2 Results (System-wide Multiple Element Screening)

PSS/E activity ACCC was used as a screening tool on each of the base cases to identify those multiple element contingencies which deserve closer study. ACCC analyzed the system by sequentially taking select multiple element contingencies in the Nebraska area out-of-service. Transmission facilities in the NPPD, OPPD, and LES areas were then monitored for violations of loading or bus voltage criteria. The Phase 2 ACCC analysis is performed to assess the performance of the transmission system following the addition of the generation interconnection projects and proposed new network upgrades according to TPL-003 and TPL-004 standards.

Phase 2 – 2016 Spring

Category C Results (TPL-003):

There were no impacted facility overloads or bus voltages discovered outside of limits under Category C contingency conditions for the 2016 Spring model.

Category D Results (TPL-004):

There were no impacted facility overloads or bus voltages discovered outside of limits under Category D contingency conditions for the 2016 Spring model.

Phase 2 – 2016 Summer Peak

Category C Results (TPL-003):

The North Platte – Stockville 115 kV line was found to overload for loss of the GGS – Red Willow 345 kV and GGS – Sweetwater 345 kV #2 double circuit (120.4%). Without the new wind projects, this overload would be 119.0% so the impact to the constraint is less than the cutoff threshold. This residual impact should be noted as it does adversely impact the constraint and could be an issue in transmission service studies and/or real-time operations.

There were no impacted bus voltages discovered outside of limits under Category C contingency conditions for the 2016 Summer Peak model.

Category D Results (TPL-004):

There were no impacted facility overloads or bus voltages discovered outside of limits under Category D contingency conditions for the 2016 Summer Peak model.

Phase 2 – 2016 Winter Peak

Category C Results (TPL-003):

There were no impacted facility overloads or bus voltages discovered outside of limits under Category C contingency conditions for the 2016 Winter Peak model.

Category D Results (TPL-004):

There were no impacted facility overloads or bus voltages discovered outside of limits under Category D contingency conditions for the 2016 Winter Peak model.

Phase 2 – 2020 Spring

Category C Results (TPL-003):

There were no impacted facility overloads or bus voltages discovered outside of limits under Category C contingency conditions for the 2020 Spring model.

Category D Results (TPL-004):

There were no impacted facility overloads or bus voltages discovered outside of limits under Category D contingency conditions for the 2020 Spring model.

Phase 2 – 2020 Summer Peak

Category C Results (TPL-003):

There were no impacted facility overloads or bus voltages discovered outside of limits under Category C contingency conditions for the 2020 Summer Peak model.

Category D Results (TPL-004):

There were no impacted facility overloads or bus voltages discovered outside of limits under Category D contingency conditions for the 2020 Summer Peak model.

Phase 2 – 2020 Winter Peak

Category C Results (TPL-003):

There were no impacted facility overloads or bus voltages discovered outside of limits under Category C contingency conditions for the 2020 Winter Peak model.

Category D Results (TPL-004):

There were no impacted facility overloads or bus voltages discovered outside of limits under Category D contingency conditions for the 2020 Winter Peak model.

Phase 2 Results Summary

The Phase 2 screening did not identify any significantly impacted facilities for Category C or Category D conditions. The North Platte – Stockville 115 kV line was identified as an impacted constraint, however, the impact was less than the cutoff threshold for generation interconnection studies. The Phase 2 screening did not discover any impacted bus voltages outside of limits for Category C or Category D conditions.

5.3 Phase 3 Results (Local Area Full Accredited Generation Capacity N-1 & N-2 Contingency Analysis)

5.3.1 Phase 3 – N-1 Contingency Screening Analysis Results

PSS/E activity ACCC was used as a screening tool on the maximum generation powerflow model to identify those contingencies which deserve closer study. It should be noted that the powerflow models utilized in this phase of the loadflow study represent extreme worst-case generation outlet conditions. The powerflow models represent a highly unlikely maximum simultaneous generation dispatch scenario of generation facilities in the area. ACCC was utilized to analyze the system by sequentially taking contingencies in the NPPD, LES, and OPPD area out-of-service and monitoring facilities in the NPPD, LES, and OPPD area for violations of loading or bus voltage criteria.

Phase 3 – 2016 Winter Peak – Maximum Generation (N-1)

System Intact Results (TPL-001):

There were no transmission facility overloads or bus voltages outside of limits under system intact or base case conditions for the 2016 Winter Peak – Maximum Generation model.

N-1 Contingency Results (TPL-002):

There were no impacted transmission facility overloads or bus voltages discovered outside of limits under N-1 conditions for the 2016 Winter Peak – Maximum Generation model.

5.3.2 Phase 3 – Multiple Element Contingency Analysis Results

This phase of the analysis evaluated all worst-case stuck breaker and double circuit contingencies in the Nebraska area. PSS/E activity ACCC was used as a screening tool on the maximum generation base case with the additions to identify those contingencies which deserve closer study. ACCC analyzed the system by sequentially taking stuck breaker and double circuit contingencies in the Nebraska area and monitoring facilities in the NPPD, OPPD, and LES areas for violations of loading or bus voltage criteria.

Phase 3 – 2016 Winter Peak – Maximum Generation (Stuck PCB / Double Circuit / Extreme)

Category C Results (TPL-003):

<u>Facility</u>	<u>Contingency</u>	<u>Rating</u>	<u>Loading</u>
N.Platte-Stockville 115kV	GGs-Red Willow & GGS-SW 345kV	137 MVA	117.5%
GGs 345/230kV	GGs PCB 3306	336 MVA	120.4%
Red Willow-Mingo 345kV	Axtell PCB 3306	785 MVA	101.1%

There were no impacted bus voltages outside of limits under Category C conditions for the 2016 Winter Peak – Maximum Generation model.

Category D Results (TPL-004):

<u>Facility</u>	<u>Contingency</u>	<u>Rating</u>	<u>Loading</u>
N.Platte-Stockville 115kV	GGs 345kV substation	137 MVA	112.3%
Red Willow-Mingo 345kV	Sweetwater 345kV substation	785 MVA	110.0%

There were no impacted bus voltages outside of limits under Category D conditions for the 2016 Winter Peak – Maximum Generation model.

5.3.3 Phase 3 – Independent N-2 Contingency Analysis Results

This phase of the analysis evaluated select set of independent N-2 contingencies in the local area of the generation interconnection projects. PSS/E activity ACCC was used as a screening tool on the 2014 Winter Peak Maximum Generation powerflow model with the generation interconnection projects to identify those contingencies which deserve closer study. ACCC analyzed the system by sequentially taking out all independent N-2 contingencies in the local area and monitoring facilities in the NPPD, OPPD, and LES areas for violations of loading or bus voltage criteria. A total of 1498 independent N-2 contingencies were included in this contingency analysis.

Phase 3 – 2016 Winter Peak – Maximum Generation (Independent N-2)

There were a number of overloaded transmission facilities discovered in the monitored study areas in the independent N-2 ACCC analysis of the 2016 Winter Peak Maximum Generation case with the generation interconnection addition. Prior outage generation restrictions would be required to ensure the transmission system is able to be operated reliably when certain transmission lines are taken out-of-service. The generation interconnection project curtailments will be subject to “first on, last off” curtailment priorities and operating guides will need to be developed to ensure the transmission system is operated in accordance with mandatory reliability standards. Based on a review of the N-2 contingencies that were flagged in the ACCC analysis, the following list was prepared of transmission facilities that would need detailed prior outage review or

operating guides established if all the projects are developed. These transmission facilities were found to be part of an N-2 contingency pairing that resulted in a facility overload on the NPPD transmission system.

Limiting Prior Outage Facilities

1. Bloomfield – Gavins Point 115 kV
2. Neligh East – Hoskins 345 kV
3. Neligh East 345/115 kV Transformer
4. Neligh East – County Line 115 kV
5. North Hebron – Fairbury 115 kV
6. North Hebron – Carleton Junction 115 kV
7. Gavins Point – Yankton Junction 115 kV
8. Gavins Point – Spirit Mound 115 kV

Phase 3 Results Summary

Overall, there were no impacted transmission facility overloads or bus voltages outside of limits discovered in the Phase 3 screening for NERC category A, B, C, and D contingencies. There were several category C and D contingencies that resulted in facility overloads that were impacted; however, the impact was less than the cutoff threshold for generation interconnection studies. These facility overloads were documented in the facility study. There were several independent N-2 contingencies that resulted in overloads and would require prior-outage generation limitations to mitigate the identified issues if all the proposed projects are developed.

5.4 Phase 4 Results (System-wide N-1 Screening w/ transfer conditions)

The Phase 4 ACCC analysis is performed to assess the performance of the transmission system under stressed heavy transfer conditions following the addition of the generation interconnection projects according to TPL-001 and TPL-002 standards. This phase utilized the 2016 Spring Peak case as the base system topology. Generation in western Nebraska and Iowa were then increased to stress the existing north-south flowgates (WNE_WKS & COOPER_S) in Nebraska to existing transfer limits. PSS/E activity ACCC was then used as a screening tool on the base case to identify those contingencies which deserve closer study. ACCC analyzed the system by sequentially taking each transmission element greater than 100kV in the NPPD, OPPD, and LES areas out of service. Transmission facilities in the NPPD, OPPD, and LES areas were then monitored for violations of loading or bus voltage criteria. Contingencies which resulted in facility loadings or bus voltages outside of acceptable limits will be discussed in the summary of each case.

System Intact Results (TPL-001):

The Red Willow – Mingo 345 kV line was overloaded to 106.4% of the 785 MVA facility rating and the bus voltages at Red Willow, Mingo and Post Rock 345 kV substation were 0.929, 0.920, and 0.941 per unit, respectively. This is a highly stressed north-south transfer case with the north-south ties in western Nebraska / western Kansas pushed to beyond its limits. The additional generation interconnected north of these constraints will only put more pressure on this area of the system in the future.

N-1 Contingency Results (TPL-002):

Multiple overloaded transmission facilities were discovered in the monitored study areas in the N-1 ACCC analysis of the 2014 Winter Peak case with transfers and the generation interconnection projects. These facility overloads are listed below:

<u>Facility</u>	<u>Contingency</u>	<u>Rating</u>	<u>Loading</u>
N.Platte-Stockville 115kV	GGs-Red Willow 345kV	137 MVA	143.7%
Stockville-RedWillow 115kV	GGs-Red Willow 345kV	137 MVA	126.8%
Beverly-Enders 115kV	GGs-Red Willow 345kV	160 MVA	107.8%
Grant-Enders 115kV	GGs-Red Willow 345kV	120 MVA	105.7%
Red Willow 345/115kV	GGs-Red Willow 345kV	336 MVA	117.2%
Red Willow-Mingo 345kV	Post Rock-Axtell 345kV	785 MVA	136.5% ^A
Ogallala-Sidney 230kV	Sidney-Keystone 345kV	320 MVA	134.8% ^B
GGs-Ogallala 230kV	GGs-Keystone 345kV	320 MVA	102.4% ^B
GGs 345/230kV T1	GGs-Keystone 345kV	336 MVA	100.1% ^B

A - Only worst-case contingency listed in summary table

B - Loading mitigated through implementation of Sidney DC RAS

The bus voltages in western Nebraska are also severely stressed for worst-case contingencies listed above. Voltages on the 345 kV and 115 kV systems in the area are depressed to as low as 0.83-0.84 per unit for the GGs-Red Willow 345 kV and Post Rock-Axtell 345 kV contingencies.

The future ~220-mile GGS – Thedford – Holt 345 kV ITP10 project will help provide some marginal relief to these north-south constraints, however, it won't fully relieve the overloads or voltage issues highlighted in this section of the facility study. The GGS Thedford – Holt 345 kV provides a new west-to-east 345 kV path across Nebraska that helps relieve the flows on the existing west-to-east transmission system, but the prevailing north-to-south flows are marginally affected. The future Nebraska City – Sibley 345 kV line in eastern Nebraska will also provide some marginal relief to the north-south limitations in western Nebraska and western Kansas, but this relief should be minimal.

Phase 4 Results Summary

Overall, there were multiple transmission facility overloads and voltage issues discovered in the Phase 4 screening that were associated with west-east and north-south transfer limitations in Nebraska. The limitations are expected to be marginally improved by the future transmission projects being developed in Nebraska (GGS-Thedford-Holt 345 kV, Nebraska City-Sibley 345 kV), however, these constraint relief benefits should be minimal and the issues documented in this phase of the study will persist if all the proposed generation interconnection projects move forward.

6.0 Short Circuit Study

6.1 Model Development

Computer Programs

The Aspen OneLiner software program was utilized to perform short circuit simulations and studies on the transmission system. Standard procedures that the transmission system protection department uses for short-circuit studies were used for short-circuit calculations for this study. Where elements were added to the short-circuit model, best estimates for impedance parameters were used based on available data and typical modeling practices.

Base System Model Additions (“Base Case”)

The base system model used by the transmission system protection department as of December 8, 2014 was used as the starting point for the short-circuit model used for this study. The base system model included all projects that were in-service at the time the model was copied. For the study base case, planned system upgrades in the area of the studied projects and prior-queued large generator interconnections expected to be in-service prior to the projects being studied were added to the base case model. Table 1 lists the prior-queued large generator interconnections that were added to the base model for this study.

Table 1: Prior Queued Large Generator Interconnections

Queue Designation	Proposed POI	Capacity (MW)
GEN-2008-123N GEN-2013-014	Rosemont 115 kV (New substation)	115.2
GEN-2010-051	Wakefield 230 kV (New substation)	200
GEN-2011-027	Wakefield 230 kV (New substation)	120
GEN-2013-008	Steele City 115 kV (Add to existing 34.5 kV collector bus)	1.2
GEN-2013-032	Antelope 115 kV (Expand new substation)	204

Along with the prior-queued large generator interconnections, system upgrades previously identified to accommodate the prior-queued projects were added to the study model. The upgrades previously identified included the following additions:

- Antelope – Tilden – Battle Creek 115 kV line upgrade

In addition to the prior-queued large generator interconnections, planned system upgrades in the area of the studied projects were added to the base model. For this study, the upgrades associated with the Antelope 115 kV – 345 kV substation were included in the model, including the four re-routed 115 kV lines into the new Antelope Substation, the one new 345 kV line from Hoskins to Antelope, and a new 345 kV – 115 kV auto

transformer at the new Antelope Substation. The planned 345 kV line from GGS – Thedford – Holt County was included with a 345 – 115 kV tie transformer at Thedford 115 kV. The planned 115 kV line from Ord to Broken Bow Wind/Muddy Creek substation was included.

Model Additions for Projects Being Studied (“Study Case”)

The base-case study model was modified to include the new generation interconnections being considered in this study as well as the system upgrades identified to accommodate this additional generation. Table 2 lists the large generator interconnections that were added to the study-case model for this study.

Table 2: Large Generator Interconnections Added to Study Case

Queue Designation	Proposed POI	Capacity (MW)
GEN-2014-004	Steele City 115 kV (Add to existing 34.5 kV collector bus)	3.96
GEN-2014-013	Prairie Breeze 230 kV	73.5

No network upgrades associated with the generator interconnections being studied were included with this study.

6.2 Study Methodology

The portion of the system potentially impacted by the projects being considered in this study was determined by identifying buses at which the available fault current increased by more than 5% between the base case and the study case. For buses identified as potentially impacted by these projects, the equipment connected at those buses was examined to determine if the additional fault current exceeded the interrupting or short circuit current capability of the equipment.

To allow for modeling errors, all protective devices within 90% of their interrupting rating or short-circuit capability will be identified. It is recommended that all breakers/fuses within 95% of the nameplate interrupting rating or short-circuit capacity be replaced unless otherwise noted.

6.3 Results

No devices were found to be above 95% of their interrupting rating or short-circuit capability due to the addition of the projects considered in this study.

7.0 Detailed Cost Estimates & Project Schedule

NPPD reviewed the list of projects required for the DISIS-2014-001-1 generation interconnection projects and determined that no additional cost estimates or project schedules would be required for this facility study. There were no network upgrades identified in the SPP DISIS or the NPPD facility study that were required solely due to the generation interconnection projects in the DISIS-2014-001-1 study.